

＜ 数 量 総 括 表 ＞

仲間川サキシマスオウノキ遊歩道整備工事(2工区)

[illegible][illegible]

[illegible]

数 量 計 算 書

仲間川サキシマスオウノキ遊歩道整備工事(2工区)

名 称	材 料	計 算 式	数 量	単位
遊歩道重量	W=1.3m L=42.6m			
支柱	GRP(角形)t=8 0.10*0.10	0.66*2+0.47*2+0.44*2+0.43*2+0.40*2+0.34*2		
		+ 0.31*12+0.43*2+0.39*2+0.35*2+0.36*4+0.37*2		
		+ 0.38*2+0.37*2+0.31*2 = 15.84		
		15.84*7.50 = 118.80		
横桁	GRP(溝形)t=10 0.05*0.20	1.51*14+1.81+1.51*26+1.52 = 63.73		
		63.73*5.30 = 337.77		
吊大引	GRP(溝形)t=10 0.05*0.20	0.41*32+0.28 = 13.40		
		13.40*5.30 = 71.02		
縦桁	GRP(溝形)t=10 0.05*0.20	1.00*4+1.86*8+0.91*8+2.36*8+0.37*3+2.36*4		
		+ 1.06*8+2.36*4+0.96*4+1.69*4+2.36*28+1.75*4		
		+ 1.97+0.97 = 160.13		
		160.13*5.30 = 848.69		
根太	GRP(角形)t=6 0.05*0.05	1.08*4+2.00*8+1.08*8+2.50*8+0.45*3+1.80+2.55*4		
		+ 1.23*8+2.50*4+1.13*4+1.86*4+2.50*28+1.89*4		

名 称	材 料	計 算 式	数 量	単位
		+ 2.18+1.00 = 174.85		
		174.85*2.00 = 349.70		
床板	CTWOOD 0.03*0.145	1.346*274+1.82*13+0.63*3+0.45*3 = 395.70		
		395.70*4.02 = 1,590.71		
手摺柱	GRP(角形)t=8 0.075*0.075	1.13*85*4.09 = 392.84		
笠木	GRP t=8 0.092*0.055	2.42*2+2.32*2+1.34*2+1.70*2+2.50*2+2.28+2.33		
		+ 1.47+2.05+0.63+1.86*4+2.25*2+0.76*2+1.24*2		
		+ 2.50*14+2.60+0.58+2.49 = 85.93		
		85.93*2.69 = 231.15		
横棧	GRP(D型) t=5 0.035*0.075	1.09*6+1.08*18+0.61*6+0.88*3+0.25*3+0.66*3		
		+ 0.92*6+1.17*18+0.96*6+0.63*6+0.68*3+0.50*3		
		+ 1.17*3+0.92*6+0.36*3+0.85*3+0.36*3+0.85*3		
		+ 0.92*12+1.17*6+0.42*3+0.61*3+0.90*3+1.09*3		
		+ 1.17*87+1.04*3+0.40*3+1.03*3+1.06*3+0.11*6		
		+ 0.14*6+0.11*6+0.14*6+0.12*6+0.13*6+0.05*3		

